

PROJECT TITLE:

TOWN OF HOPKINTON

**PARKING LOT RENOVATION OF THE
 1904 ASHAWAY SCHOOL BUILDING
 12 HILLSIDE AVENUE
 HOPKINTON, RHODE ISLAND**

PREPARED FOR:

TOWN OF HOPKINTON

**CRANDALL HOUSE
 188 MAIN STREET
 ASHAWAY, RHODE ISLAND**

DRAWING TITLE:

SITE LAYOUT PLAN

DATE: DECEMBER 2024 SCALE: 1"=20'

DWG. NAME: 2349.106-04-SITE.dwg

REVISIONS		
NUMBER	REMARKS	DATE

DRAWING NUMBER

C3

SHEET: 4 OF 5

GENERAL NOTES

1. ALL MILLINGS SHALL REMAIN THE PROPERTY OF THE OWNER. THE CONTRACTOR SHALL BE RESPONSIBLE FOR LOADING AND HAULING THE MILLING MATERIAL TO A LOCATION IN THE TOWN OF HOPKINTON, AS DETERMINED BY THE OWNER, AT THE CONTRACTOR'S EXPENSE AND NO ADDITIONAL COST TO THE OWNER. THE DEPTH OF MILLINGS TO BE REMOVED UNDER NEW PAVEMENT AREAS IS 15 INCHES. THE DEPTH OF MILLINGS TO BE REMOVED UNDER THE NEW LOAM AREAS IS 4 INCHES.
2. CONTRACTOR SHALL SUBMIT A SHOP DRAWING OF THE CHAIN LINK FENCE TO THE OWNER FOR APPROVAL PRIOR TO ORDERING.
3. THE CONTRACTOR IS MADE AWARE THAN AN EXISTING PARKING LOT EXISTS IN THE BACK OF THE EXISTING BUILDING IN THIS AREA. ACCESS TO THIS AREA IS REQUIRED DURING ALL NORMAL SCHOOL HOURS.

